



STATION [m]	GEWÄSSERSOHL [mNN]	LINKES UFER [mNN]	RECHTES UFER [mNN]	MQ PLAN [mNN]	MQ IST [mNN]
0+00	67.85	70.12	70.54	69.17	69.17
50+00	67.97	70.24	70.66	69.20	69.20
90+00	67.97	70.24	70.66	69.22	69.22
100+00	68.09	70.36	70.78	69.22	69.22
150+00	68.21	70.48	70.90	69.30	69.30
200+00	68.33	70.60	71.02	69.42	69.42
250+00	68.45	70.72	71.14	69.54	69.54
259+00	68.47	70.74	71.16	69.56	69.56
300+00	68.54	70.88	71.18	69.62	69.62
350+00	68.62	71.05	71.20	69.67	69.67
400+00	68.71	71.22	71.22	69.71	69.71
450+00	68.79	71.39	71.24	69.74	69.74
500+00	68.88	71.56	71.26	69.77	69.77
550+00	68.96	71.73	71.28	69.80	69.80
590+00	69.03	71.87	71.30	69.81	69.81
600+00	69.04	71.87	71.27	69.82	69.82
650+00	69.07	71.88	71.13	69.85	69.85
700+00	69.10	71.88	71.46	69.90	69.90
750+00	69.13	71.89	71.40	69.99	69.99
800+00	69.17	71.89	71.35	70.10	70.10
850+00	69.20	71.74	71.30	70.15	70.15
880+00	69.20	71.74	71.30	70.14	70.14
895+00	69.26	71.80	71.36	70.16	70.16
904.50	69.26	71.80	71.36	70.19	70.19
950+00	69.33	71.70	71.38	70.21	70.21
1000+00	69.40	71.58	71.07	70.25	70.25
1050+00	69.48	71.46	71.31	70.31	70.31
1077+00	69.51	70.59	71.34	70.32	70.32
1085.50	69.54	71.32	71.55	70.38	70.37
1104+00	69.56	71.34	71.57	70.46	70.46
1150+00	69.60	71.43	71.50	70.49	70.49
1200+00	69.72	71.27	71.77	70.52	70.52
1250+00	69.84	71.80	72.03	70.64	70.55
1300+00	69.78	71.78	72.29	70.68	70.60
1327+00	69.74	72.52	72.43	70.68	70.61
1350+00	69.78	72.49	72.40	70.68	70.61
1400+00	69.87	72.42	72.33	70.70	70.64
1450+00	69.95	72.35	72.26	70.74	70.70
1500+00	70.04	72.28	72.19	70.83	70.77
1550+00	70.10	72.17	72.12	70.93	70.80
1600+00	70.07	72.26	72.05	70.95	70.83
1650+00	70.08	72.35	71.98	70.97	70.89
1661+00	70.09	72.40	71.94	70.98	70.91
1675+00	70.09	72.40	71.94	70.99	70.92
1700+00	70.16	72.38	71.96	71.03	70.94
1750+00	70.24	72.26	71.93	71.09	70.98
1761+00	70.27	72.29	71.96	71.08	70.97
1771+00	70.27	72.29	71.94	71.08	70.97
1800+00	70.27	72.29	71.94	71.11	71.02
1852+00	70.23	72.24	72.26	71.12	71.04
1900+00	70.26	72.16	72.16	71.13	71.07
1950+00	70.29	72.07	72.06	71.22	71.11
2000+00	70.32	72.73	72.66	71.27	71.22
2037+00	70.32	72.73	72.66	71.29	71.26
2071+00	70.36	73.06	73.04	71.35	71.33
2082+00	70.36	73.06	73.04	71.36	71.35
2095.50	70.37	73.06	73.05	71.42	71.41
2100+00	70.37	73.06	73.05	71.43	71.43
2150+00	70.50	73.22	73.21	71.45	71.43
2200+00	70.65	73.37	73.36	71.57	71.47
2250+00	70.80	73.52	73.51	71.62	71.58
2259+00	70.85	73.11	74.66	71.61	71.57
2297+00	70.85	73.11	74.66	71.67	71.64
2350+00	70.90	73.95	74.26	71.66	71.62
2366+00	70.94	72.83	73.88	71.68	71.65
2400+00	70.96	72.55	73.67	71.78	71.73
2450+00	71.00	72.53	73.37	71.89	71.79
2500+00	71.03	72.50	73.06	71.91	71.82
2532+00	71.03	72.50	73.06	71.92	71.84
2543+00	71.05	72.45	72.74	71.93	71.86
2550+00	71.07	72.47	72.74	71.93	71.86

Projekt	: Gewässerentwicklungskonzept	
	Wabe / Mittelriede	
Längsschnitt	Mittelriede (Unterlauf) - MQ	
Abschnitt	: Km 0+000 - Km 2+550	
Auftraggeber	: aquaplanner Ingenieurgesellschaft	
Auftragnehmer	: HGN Hydrogeologie GmbH	
Maßstäbe:	Anlage	: 1
Länge 1:	2500	Blatt
Höhe 1:	100	Datum
		: 20.03.2008